

AD-A087 329

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/13
NATIONAL DAM SAFETY PROGRAM. ELECTRIC LIGHT POND DAM (NJ00245).--ETC(U)
FEB 80 J TALERICO DACW61-79-C-0011


UNCLASSIFIED

1 of 2
000-130




U

NI



08732



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

ADA 087329

HACKENSACK RIVER BASIN
PASCACK BROOK, BERGEN COUNTY
NEW JERSEY

ELECTRIC LIGHT POND DAM

NJ 00245

DTIC
ELECTE
JUL 31 1980

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

THIS DOCUMENT IS BEST QUALITY PRACTICAL
THE COPY CONTAINED TO DDC CONTAINED A
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT
REPRODUCE EXACTLY.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

FEBRUARY 1980

80 7 25 135

NOTICE

**THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED BY
THE SPONSORING AGENCY. ALTHOUGH
IT IS RECOGNIZED THAT CERTAIN POR-
TIONS ARE ILLEGIBLE, IT IS BEING
RELEASED IN THE INTEREST OF MAKING
AVAILABLE AS MUCH INFORMATION AS
POSSIBLE.**

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00245	2. GOVT ACCESSION NO. AD-A087329	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Electric Light Pond Dam (NJ00245), Electric Bergen County, NJ		5. TYPE OF REPORT & PERIOD COVERED (9) FINAL rept.
7. AUTHOR(s) John Talerico Hackensack River Basin, Passaic Brook, Bergen County, New Jersey. Phase		8. CONTRACT OR GRANT NUMBER(s) (15) DACW61-79-C-0011
9. PERFORMING ORGANIZATION NAME AND ADDRESS Fredric R. Harris, Inc. 1 Inspection 453 Amboy Ave. Woodbridge, NJ 07095 Report.		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS (12) 118
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CN029 Trenton, NJ 08625		12. REPORT DATE (11) Feb 80
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106 (10) John/Talerico		13. NUMBER OF PAGES 101
15. SECURITY CLASS. (of this report) Unclassified		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams National Dam Safety Program Dam Safety Electric Light Pond Dam, NJ Visual Inspection Structural analysis Spillways		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

410891 JCM

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

CONFIDENTIAL

(1)

CONFIDENTIAL

SECRET

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



IN REPLY REFER TO
NAPEN-N

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

21 JUL 1960

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist.	Availand/or special
A	2

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Electric Light Pond Dam in Bergen County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Electric Light Pond Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's three spillways are considered inadequate because a flow equivalent to 91 percent of the Spillway Design Flood -SDF- would cause the dam to be overtopped. The SDF, in this instance, is one half of the Probable Maximum Flood (PMF). The decision to consider the spillways inadequate instead of seriously inadequate is based on the determination that overtopping of the dam would not significantly increase the hazard to loss of life downstream from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillways' adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within twelve months from the date of approval of this report. This should include the installation of a tailwater gage and a determination of the ability of the dam to withstand overtopping. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. The following remedial actions should be completed within twelve months from the date of approval of this report:

(1) Investigate the embankment for animal burrows and fill in the burrows with an impervious material.

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

NAPEN-N

Honorable Brendan T. Byrne

(2) Repair all eroded, cracked and spalled concrete with epoxy cement.

(3) Clean and repaint all the steel-work on the operating mechanisms. Repair the stem stand concrete support and install a new valve at the west spillway.

(4) Install new discharge conduit at the west spillway.

(5) Install an access bridge across the east spillway and install a new sluice gate with the operating mechanism located on the access bridge.

(6) All brush and trees should be removed from the downstream slope and emergency spillway to avoid problems which may develop from their roots. The embankment should then be seeded to develop a growth of grass for surface erosion protection.

(7) The owner should inspect the dam for seepage during the refilling operation.

c. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months from the date of approval of this report.

d. Within one year from the date of approval of this report the owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Harold Hollenbeck of the Ninth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.


Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

NAPEN-N

Honorable Brendan T. Byrne

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



JAMES G. TON
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Copies furnished:
Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

ELECTRIC LIGHT POND DAM (NJ00245)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 12 November and 3 December 1979 by Harris-ECI Associates, Inc., under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Electric Light Pond Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's three spillways are considered inadequate because a flow equivalent to 91 percent of the Spillway Design Flood -SDF- would cause the dam to be overtopped. The SDF, in this instance, is one half of the Probable Maximum Flood (PMF). The decision to consider the spillways inadequate instead of seriously inadequate is based on the determination that overtopping of the dam would not significantly increase the hazard to loss of life downstream from that which would exist just before overtopping failure. To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillways' adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within twelve months from the date of approval of this report. This should include the installation of a tailwater gage and a determination of the ability of the dam to withstand overtopping. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. The following remedial actions should be completed within twelve months from the date of approval of this report:

(1) Investigate the embankment for animal burrows and fill in the burrows with an impervious material.

(2) Repair all eroded, cracked and spalled concrete with epoxy cement.

(3) Clean and repaint all the steel-work on the operating mechanisms. Repair the stem stand concrete support and install a new valve at the west spillway.

(4) Install new discharge conduit at the west spillway.

(5) Install an access bridge across the east spillway and install a new sluice gate with the operating mechanism located on the access bridge.

(6) All brush and trees should be removed from the downstream slope and emergency spillway to avoid problems which may develop from their roots. The embankment should then be seeded to develop a growth of grass for surface erosion protection.

(7) The owner should inspect the dam for seepage during the refilling operation.

c. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months from the date of approval of this report.

d. Within one year from the date of approval of this report the owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

APPROVED:

James G. Ton
JAMES G. TON

Colonel, Corps of Engineers
District Engineer

DATE:

7 July 1980

HACKENSACK RIVER BASIN
PASCACK BROOK, BERGEN COUNTY
NEW JERSEY

ELECTRIC LIGHT POND DAM

NJ00245

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA 19106

JANUARY, 1980

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name: Electric Light Pond Dam, I.D. NJ 00245
State Located: New Jersey
County Located: Bergen
Stream: Pascack Brook
River Basin: Hackensack River
Date of Inspection: November 12 and December 3, 1979

Assessment of General Condition

Electric Light Pond Dam is an earthfill embankment dam containing a west spillway, an east spillway, and just right of the east spillway, an emergency spillway. The overall condition of the dam is considered fair. There is no major sign of distress or instability of the embankment although minor surface cracks were noted in the emergency spillway. The operating mechanism for the east spillway low level outlet is missing, and at the time of inspection, the west spillway outlet control was not operative. The hazard potential is rated as "high".

The adequacy of Electric Light Pond Dam is considered questionable in view of its lack of spillway capacity to pass the SDF (1/2 PMF) without overtopping the dam. The spillway is capable of passing a flood equal to 45 percent of the PMF (90 percent of the 1/2 PMF), and is rated "inadequate".

At present, the engineering data available is not sufficient to make a definitive statement on the stability of the dam. The following actions, therefore, are recommended along with a timetable for their completion. All recommended studies should be conducted by an engineer qualified in the design and construction of dams.

1. Carry out a more precise hydrologic and hydraulic analysis of the dam within twelve months, to determine the need and type of mitigating measures necessary. Based on the results of these studies, remedial measures should be instituted. This should include the installation of a tailwater gage.
2. Investigate embankment for animal burrows and fill in the burrows with an impervious material.

3. Repair all eroded, cracked and spalled concrete with epoxy cement, within twelve months.
4. Clean and repaint all the steel-work on the operating mechanisms. Repair stem stand concrete support and install a new valve at the west spillway. This work should be completed within twelve months.
5. Install new discharge conduit at west spillway, within twelve months.
6. Install access bridge across east spillway and install new sluice gate with operating mechanism located on access bridge, within twelve months.
7. All brush and trees should be removed from the downstream slope and emergency spillway to avoid problems which may develop from their roots. The embankment should then be seeded to develop a growth of grass for surface erosion protection. This program should be started within twelve months.
8. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months.
9. The owner should inspect the dam for seepage during the refilling operation.

Furthermore, while of a less urgent nature, the following additional action is recommended and should be carried out within twenty-four months.

The owner should develop within one (1) year after formal approval of the report, written operating procedures and a periodic maintenance plan to insure the safety of the dam.


John P. Talerico, P.E.
HARRIS-ECI ASSOCIATES



Photo taken on February 8, 1980

ELECTRIC LIGHT POND DAM

View from East spillway (portion of right abutment in foreground) toward Emergency spillway, embankment, West spillway and abandoned powerhouse to its right. Water in the reservoir, right, has been drained for dry dredging operations.

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the office of the Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

ASSESSMENT OF GENERAL CONDITIONS

OVERVIEW PHOTO

PREFACE

Page

SECTION 1	PROJECT INFORMATION	1
	1.1 General	1
	1.2 Description of Project	1
	1.3 Pertinent Data	5
SECTION 2	ENGINEERING DATA.....	8
	2.1 Design	8
	2.2 Construction.....	8
	2.3 Operation	8
	2.4 Evaluation.....	8
SECTION 3	VISUAL INSPECTION.....	9
	3.1 Findings	9
SECTION 4	OPERATION PROCEDURES.....	11
	4.1 Procedures	11
	4.2 Maintenance of Dam.....	11
	4.3 Maintenance of Operating Facilities.....	11
	4.4 Evaluation	11
SECTION 5	HYDRAULIC/HYDROLOGIC	12
	5.1 Evaluation of Features.....	12
SECTION 6	STRUCTURAL STABILITY	14
	6.1 Evaluation of Structural Stability.....	14
SECTION 7	ASSESSMENT/REMEDIAL MEASURES	16
	7.1 Dam Assessment	16
	7.2 Remedial Measures	17

TABLE OF CONTENTS CONTINUED

PLATES

	<u>No.</u>
KEY MAP AND VICINITY MAP	1 & 1A
GEOLOGIC MAP.....	2
DRAWINGS OF DAM.....	3-10

APPENDICES

APPENDIX A - CHECK LIST - VISUAL OBSERVATIONS CHECK LIST - ENGINEERING, CONSTRUCTION, MAINTENANCE DATA	1- 14
APPENDIX B - PHOTOGRAPHS	
APPENDIX C - SUMMARY OF ENGINEERING DATA	1
APPENDIX D - HYDROLOGIC COMPUTATIONS.....	1 - 36

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

ELECTRIC LIGHT POND DAM, I.D. NJ00245

SECTION 1

1. PROJECT INFORMATION

1.1 General

a. Authority

The National Dam Inspection Act (Public Law 92-367, 1972) provides for the National Inventory and Inspection Program by the U.S. Army Corps of Engineers. This inspection was made in accordance with this authority under Contract C-FPM No. 35 with the State of New Jersey who, in turn, is contracted to the Philadelphia District of the Corps of Engineers, and was carried out by the engineering firm of Harris-ECI Associates, Woodbridge, New Jersey.

b. Purpose of Inspection

The visual inspection of Electric Light Pond Dam was made on November 12, 1979. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

The report summarizes available pertinent data relating to the project; presents a summary of visual observations made during the field inspections; presents an evaluation of hydrologic and hydraulic conditions at the site; presents an evaluation as to the structural adequacy of the various project features; and assesses the general condition of the dam with respect to safety.

1.2 Description of Project

a. Description of Dam and Appurtenances

Electric Light Pond Dam is an earthfill dam approximately 588 feet long and 20.6 feet high with two main spillways and one emergency spillway. The main spillways are located at the east and west end of the dam with the emergency spillway located immediately west of the east spillway. The top of the embankment is 12 feet wide and the upstream and downstream faces are sloped at 2.5H: 1V and 2H: 1V, respectively. A 12-inch wide concrete core wall extends from the west spillway 94 feet into the embankment.

The main spillways are ungated modified concrete ogee overflows with crest elevations 5.6 feet below the top of the embankment. The east spillway is 20.0 feet wide while the west spillway is 47 feet wide and is reinforced by two concrete buttresses. The emergency concrete spillway which was constructed over the section of embankment that failed in 1945, is 66 feet wide with a crest elevation 2.5 feet above the main spillways. A steel sheeting cutoff wall is located under the emergency spillway and extends 21 feet into the embankment.

Two 48-inch concrete pipes located at the east and west spillways are used to lower the lake. They are controlled by sluice gates on the upstream face of the dam. The discharge through the east spillway is directly into the downstream channel while the discharge through the west spillway goes through an abandoned power house before entering the channel. The gate at the west spillway is a hand operated rising stem steel gate. There is no operating mechanism at the east spillway and the gate must be removed manually to open it.

Two boring programs were performed for this dam. In 1946, Riley Engineering and Drilling Co. drilled six holes along the dam's crest (Plate 9). An additional program was performed in 1951. A Hobelmon, Argenti, and Kuhn construction plan (Plate 10), shows four toe borings. The driller was not identified.

The six crest borings classify the embankment as sand and gravel with the foundation, generally, clay, fine sand and gravel. Rock, identified as sandstone, is greater than 20 feet below the dam's toe.

A generalized description of soil conditions is contained in Report No. 4, Bergen and Hudson Counties, Engineering Soil Survey of New Jersey, by Rutgers University. The report describes the downstream area as recent alluvium. The remaining portions of the lake is classified as stratified drift.

Recent alluvium are soils transported to their present location by surface water and stream flow. The soils range in size from clayey silt to gravelly silt and sand. They have been altered from their parent material by alluvial action and sedimentation. Stratified drift is non-residual materials deposited by the Wisconsin glacier. The drift is assorted, relatively homogeneous material, mainly sand sizes, with varying amounts of silt and gravel. The underlying rock is deep and is described on Geologic Overlay Sheet 23 as the Brunswick Formation. This formation is primarily shale with interbedded sandstone.

b. Location

Electric Light Pond Dam is located on Pascack Brook in the Borough of Park Ridge, Bergen County, New Jersey. It is approximately 1,300 ft. upstream from the Park Avenue Bridge and is accessible from Mill Avenue.

c. Size Classification

According to the "Recommended Guidelines for Safety Inspection of Dams" by the U.S. Department of the Army, Office of the Chief of Engineers, the dam is classified in the dam size category as being "small", since its storage area of 65 acre-feet is less than 1,000 acre-feet. The dam is also classified as small because its height of 20.6 feet is less than 40 feet. The overall size classification of Electric Light Pond is small.

d. Hazard Classification

A hazard potential classification of "high" has been assigned to the dam on the basis that a hypothetical failure would result in excessive damage to commercial and borough owned property downstream of the dam. In addition, the immediate downstream area is used for recreational purposes with a park, pool, and tennis courts so that the possibility exists of the loss of more than a few lives in the event of dam failure.

e. Ownership

Electric Light Pond Dam is owned by:

Borough of Park Ridge
55 Park Avenue
Park Ridge, New Jersey 07656

Attention: Mr. Charles E. Gasior
Borough Administrator
(201) 573-1800

f. Purpose

Electric Light Pond Dam is presently used for recreational and esthetic purposes only. It was originally used to generate electricity.

g. Design and Construction History

Information concerning the original dam, which was constructed around 1900, is very limited. During the July, 1945 flood, the dam was overtopped and a section of embankment failed. The extent of the damages caused by the failure are not available. In 1952, modifications and reconstruction of the existing dam began with the intention of increasing the overflow capacity. To accomplish this the two existing spillways were lowered and an emergency spillway was provided at the area of embankment failure. Construction was completed in 1954, and since then there have not been any additional modifications.

h. Normal Operation Procedures

The discharge from the pond is normally unregulated and is allowed to naturally balance discharge with inflow into the pond. There are two low-level outlets in the pond, one at the east spillway and one at the west spillway. The outlets are controlled by sluice gates which when open discharge the water through 4 ft. concrete openings. The one at the east spillway discharges directly into the downstream channel while the one at the west spillway discharges through the abandoned powerhouse into the downstream channel. The gate through the west spillway is manually operated while the gate at the east spillway is presently inoperative.

1.3 Pertinent Data

a. Drainage Area 14.2 sq.mi.

b. Discharge at Dam Site

Maximum known flood at dam site: July 23, 1945.
Height of overtop unknown.

Ungated spillway capacity at elevation of top of dam: 4,634 cfs (elev. 137.6) NGVD

Total spillway capacity at maximum pool elevation (SDF): 5,490 cfs (elev. 137.84) NGVD

c. Elevation (Feet above NGVD)

Top of dam: 137.6
Maximum pool design surcharge (SDF): 137.84
Recreation pool: 132.2
Spillway Crest - East and West: 132.0
Emergency spillway crest: 134.5
Streambed at centerline of dam: 117.0 (estimated)
Maximum tailwater - East: 120.5 (estimated)
 - West: 119.5 (estimated)

d. Reservoir

Length of maximum pool: 1,700 ft.(estimated)
Length of recreation pool: 1,400 ft.(estimated)

e. Storage (acre-feet)

Recreation pool: 22 (elevation 132.2 NGVD)
Top of dam: 63.0
Maximum pool (SDF): 65.0

f. Reservoir Surface (acres)

Top of dam: 9
Spillway crest: 7

g. Dam

Type:	Earth fill with three concrete spillways: 2 main (East & West) and one emergency spillway.
Length:	588 ft.
Height:	20.6 ft.
Top width:	12 ft.
Side slopes - Upstream:	2.5H:1V
- Downstream:	2.0H:1V
Zoning:	Unknown
Impervious core:	Concrete = 94± ft; Steel sheeting = 20± ft; and remainder is unknown
Cutoff:	None
Grout curtain:	None

h. Diversion and Regulating Tunnel

N/A

i. Spillway

Type - East and West:	Modified concrete ogee; ungated.
Emergency:	Concrete; trapezoidal; ungated.
Length of weir - East:	20 ft.
- West:	47 ft.
- Emergency:	66 ft.
Crest elevations - East and West:	132 ft. NGVD
Emergency:	134.5 ft. NGVD
Gates:	None
U.S. Channel:	Electric light pond
D/S Channel:	D/S channel from East spillway merges with D/S channel from West spillway at a distance of approx. 800 ft. from East spillway.

j. Regulating Outlets

Low level outlet:	2-48-inch pipes
Controls:	Manually operated gate valve (now, in open position)
Emergency gate:	None
Outlet:	122.2 NGVD

SECTION 2

2. ENGINEERING DATA

2.1. Design

Computations pertaining to the original construction of the dam are not available from the New Jersey Department of Environmental Protection (NJ-DEP) or from the owner. Drawings dated 1940, are on file at the Trenton office of the NJ-DEP. Also on file at the NJ-DEP are plans for reconstruction of the dam in 1952.

Some soil data is available from borings taken through the existing embankment in 1946 and in 1951. The sampling was done as part of the modification and reconstruction of the dam. In addition, other borings were taken within the pond in 1975 for the dredging of the pond. No soil properties were given for any of the borings.

2.2 Construction

No records have been found covering the original construction of the dam. However, there is information available pertaining to the repairs and modifications of the dam during 1952-1954. This information, in the form of the contract drawings, specifications and progress reports, is on microfiche at the NJ-DEP. A brief summary of the reconstruction history has been provided in Section 1.2g.

2.3 Operations

No records of operation of the dam are available. The pond is allowed to operate naturally without regulation.

2.4 Evaluation

a. Availability

The engineering data concerning the reconstruction of the dam and the boring data of the existing embankment is available from the NJ-DEP.

b. Adequacy

The engineering data available was adequate to perform hydrologic and hydraulic computations, but was insufficient to perform stability computations. A preliminary assessment could be made based on visual observations.

c. Validity

Information contained in the drawings and checked by limited field measurements appears to be valid.

SECTION 3

3. VISUAL INSPECTION

3.1 Findings

a. General

The visual inspection of Electric Light Pond Dam revealed the dam and spillways to be in fair condition and in need of repairs.

At the time of the visual inspection water in the reservoir was drained to permit dry dredging operations currently being performed. The reservoir water was being channeled into low-level outlet drains at the abandoned powerhouse near the west spillway and at the east spillway. According to the owner, the reservoir should be refilled during the summer of 1980.

b. Dam

The earth embankment appears to be sound. No surface cracking on the embankment or at the toe was noted. Erosion of the embankment was limited to a worn footpath behind the left abutment of the west spillway. No misalignment of the embankment in the horizontal or vertical plane was observed. Numerous trees, small and medium sized, are growing on top and on both sides of the embankment. No cracks or spalling of the concrete core, or parting of the steel sheeting on top of the embankment, were noticed. No seepage or sloughing was found in any portion of the downstream face of the embankment. No evidence of burrowing by animals was observed; however, at the time of the inspection the embankment was covered with leaves, therefore the possibility does exist that there may be burrow holes in the embankment.

c. Appurtenant Structures

1. Spillways

Three concrete spillways exist-one on the embankment's west side, one on its east side (emergency spillway) and one adjacent to the emergency spillway. No seepage or leakage was noticed at any of the spillways. Severe spalling was noticed at the left interface and at the two buttresses of the west spillway. Minor spalling was noticed at the right interface of the west spillway. A vertical crack was noticed in the retaining wall on the right side of the west spillway. Severe spalling and a horizontal crack were noticed on the right abutment of the east spillway. Surface cracks along the emergency spillway were noticed with trees and shrubs growing in these cracks. A longitudinal crack exists across the east spillway. Horizontal and vertical alignment of the crests of the spillways appeared good.

2. Outlet Works

There was no cracking or spalling of the concrete surfaces in the stilling basins. A four foot diameter concrete sluice way with trash rack, located at the east base of the abandoned powerhouse and west of the west spillway, is in good condition. The sluice gate for this west spillway was open for the above mentioned current dredging operations. Water through the powerhouse exits through two concrete notches (3ft. x 2 ft. & 5 ft. x 3 ft.) at the south base of the powerhouse into the channel. A four foot diameter concrete sluice way, at the west base of the east spillway, is in good condition. No sliding gate and no operating mechanism were present at the sluice way. Water through the sluice way at the east spillway exits onto a concrete apron.

The concrete foundation supporting the operating mechanism is substantially deteriorated and additional bracing (steel channels) have been added to support the stand. Also, at the time of inspection the representatives from the borough were unable to lift the hand wheel over the valve stem to demonstrate the gate operation.

d. Reservoir Area

The reservoirs' side slopes are moderate. There is no indication of slope instability. As previously mentioned, water in the reservoir was drained to permit dry dredging operations for the removal of silt buildup.

e. Downstream Channel

Two downstream channels exist--one from the west spillway and one from the east. These channels meet approximately 800 feet from the east spillway. Channels are in good condition.

Approximately 700 feet from the east spillway, 100 feet before both channels meet, a roadway bridge crosses the east channel.

SECTION 4

4. OPERATIONAL PROCEDURES

4.1 Procedures

There are no formal operating procedures established at Electric Light Pond Dam. It is used to impound water for recreational activities with the level of the lake normally being maintained by unregulated discharge over the spillways. Prior to major storms the level in the pond is lowered by opening the sluice gate in the west spillway to allow for the additional runoff.

4.2 Maintenance of the Dam

The dam is maintained by the Borough of Park Ridge. There is no program of regular inspection and maintenance of the dam and appurtenant structures.

4.3 Maintenance of Operating Facilities

The low-level outlet operating facilities consist of two sluice gates. The operating mechanism for the east gate is missing and the gate is removed manually when they need to open it. The opening and closing of the gates is the responsibility of the Electric and Water Division of the Borough.

4.4 Evaluation

The dam and pond appear to be maintained in a serviceable condition; although the concrete has been allowed to deteriorate without repair. Such repairs as recommended should be undertaken to prevent further deterioration.

SECTION 5

5. HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design

The drainage area above Electric Light Pond Dam is approximately 14.2 square miles. A drainage map of the watershed of the dam site is presented on Plate 1, Appendix D.

The topography within the basin is moderately sloped. Elevations range from approximately 640 feet above NGVD at the north end of the watershed to about 132 feet at the dam site. Land use patterns within the watershed are 50% woodland and 50% residential development scattered around the basin.

The evaluation of the hydraulic and hydrologic features of the dam and lake was based on criteria set forth in the Corps Guidelines and additional guidance provided by the Philadelphia District, Corps of Engineers. The Spillway Design Flood for the dam falls in a range of $\frac{1}{2}$ PMF to PMF. In this case, the lower end of the range, $\frac{1}{2}$ PMF, is chosen since the dam height is at the middle to lower range of the size category.

The probable maximum flood (PMF) was calculated from the probable maximum precipitation using Hydrometeorological Report No. 33 with standard reduction factors.

The unit hydrograph was determined by Snyder's Method. Snyder's peaking coefficient C_p was specified by the COE as 0.83. The synthetic unit hydrograph was developed with the aid of the HEC1-DB program.

Initial and infiltration loss rates were applied to the Probable Maximum Precipitation to obtain rainfall excesses. The rainfall excesses were applied to the unit hydrograph to obtain the PMF and various ratios of PMF utilizing program HEC1-DB.

The SDF peak outflow calculated for the dam is 5490 cfs. This value is derived from the $\frac{1}{2}$ PMF, and results in overtopping of the dam, assuming that the lake was originally at the spillway crest elevation.

The stage-outflow relation for the spillway was determined from the geometry of the spillway and dam utilizing HEC1-DB program.

The reservoir stage-storage capacity relationship was computed directly by the conic method, utilizing the HEC1-DB program. The conic method assumes that the reservoir capacity resembles a series of vertically stacked cones. The reservoir surface areas at various elevations were measured by planimeter from a U.S.G.S. Quadrangle topographic map. Reservoir storage capacity included surcharge levels exceeding the top of the dam, and the spillway rating curve was based on the assumption that the dam remains intact during routing.

A breach analysis indicates that the hazard potential for loss of life downstream, due to dam failure from overtopping, is not significantly greater than that which exists without failure.

Drawdown calculations indicate that to empty the lake to an elevation of approximately 122.2' NGVD through the two low-level sluices would take 0.9 hours, assuming a 2 cfs/square mile inflow.

b. Experience Data

No record of reservoir stage or spillway discharge are maintained for this site.

c. Visual Observation

Two downstream channels exist-one from the west spillway and one from the east-joining approximately 800 feet downstream from the east spillway. Channels are well defined with trees growing on their banks. A roadway bridge crosses the east channel approximately 700 feet from the east spillway. A municipal building, Borough of Park Ridge, a lumber yard and a recreation area are approximately 1200 feet from the east spillway.

The reservoir's side slopes are moderate and do not exhibit signs of instability. At the time of the inspection the water in the reservoir was drained to permit dry dredging operations for the removal of silt buildup.

d. Overtopping Potential

A storm of magnitude equivalent to the SDF would cause overtopping of the dam to a height of 0.27 feet. Computations indicate that the dam can pass approximately 45% of the PMF without overtopping the dam crest. Since one half the PMF is the Spillway Design Flood (SDF) for this dam, according to the Recommended Guidelines for Safety Inspection of Dams by the Corps of Engineers, the spillway capacity of the dam is assessed as "inadequate".

SECTION 6

6. STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The dam structure shows no sign of cracking, settlement or differential movement that would suggest instability. Since the pond was drained for the dredging operation it could not be determined whether or not there is seepage. Trees and brush on the top and both sides of the embankment as well as along the top of the emergency spillway could pose a threat to stability and should be removed.

b. Design and Construction Data

No design computations were uncovered during the report preparation phase. No data was obtained on the type and limits of core between the steel sheet piling and the concrete core sections. No embankment or foundation soil parameters are available for carrying out a conventional stability analysis on the embankment. No construction data or specifications relating to the degree of embankment compaction are available for use in the stability analysis.

c. Operating Records

No operating records are available relating to the stability of the dam. During the July 1945 flood, the dam was overtopped washing out a portion of the embankment near the east spillway.

d. Post-Construction Changes

A history of the dam is given in Section 1.2g. The principal changes relating to the stability of the dam are: the widening of the embankment, the lowering of the two main spillways and the construction of an emergency spillway in 1952.

e. Static Stability

A static stability analysis was not performed for Electric Light Pond Dam because the lack of data on which to base assumptions of material properties within embankment zones might produce misleading results, but based on the findings of the visual inspection, the preliminary assessment of static stability is that it is satisfactory.

f. Seismic Stability

The dam is located in Seismic Zone 1, as defined in Recommended Guidelines for Safety Inspection of Dams, prepared by the Corps of Engineers. In general, projects located in Seismic Zones 0, 1 and 2 may be assumed to present no hazard from earthquake, provided the static stability conditions are satisfactory and conventional safety margins exist. Since static stability safety factors have not been confirmed, it cannot be stated that seismic stability is satisfactory.

SECTION 7

7. ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment

a. Safety

The dam has been inspected visually and a review has been made of the available engineering data. This assessment is subject to the limitations inherent in the visual inspection procedures stipulated by the Corps of Engineers for a Phase 1 report.

The safety of Electric Light Pond dam is in question because the dam does not have adequate spillway capacity to pass the PMF or even $\frac{1}{2}$ of the PMF without overtopping. The dam's present spillway capacity is about 45% of the PMF.

Embankment overtopping will carry with it a high risk of total embankment failure by the erosive action of the overflowing water.

No definitive statement pertaining to structural safety can be made without knowledge of the phreatic surface across the embankment section, the engineering properties of the various embankment and foundation materials and their distribution or zoning throughout the dam's section.

b. Adequacy of Information

The information uncovered was adequate to perform hydrologic and hydraulic computations. The data was insufficient to perform an adequate evaluation of dam stability.

c. Urgency of Studies

Carry out a more precise hydrologic and hydraulic analysis within twelve months, to determine the need and type of mitigating measures necessary. This should include the installation of a tailwatergage, and determination of the ability of the dam to withstand overtopping.

7.2 Remedial Measures

a. Alternatives for increasing Spillway Capacity

Alternatives for increasing spillway capacity are as follows:

1. Increase the embankment height thus permitting a higher discharge to pass over the spillway and reducing the possibility of overtopping.
2. Lower the emergency spillway crest elevation.
3. Widen the emergency spillway structure.
4. A combination of any of the above alternatives

b. Recommendations to be undertaken within 12 months

1. Investigate embankment for animal burrows and fill in the burrows with an impervious material.
2. Repair all eroded, cracked and spalled concrete with epoxy cement.
3. Clean and repaint all the steel-work on the operating mechanisms. Repair stem stand concrete support and install a new valve at the west spillway.
4. Install new discharge conduit at west spillway.
5. Install access bridge across east spillway and install new sluice gate with operating mechanism located on access bridge.
6. All brush and trees should be removed from the downstream slope and emergency spillway to avoid problems which may develop from their roots. The embankment should then be seeded to develop a growth of grass for surface erosion protection.

The following additional actions are recommended:

1. The owner should develop an emergency action plan (if one is not already available) outlining actions to be taken by the operator to minimize downstream effects of an emergency and establish a flood warning system for the downstream communities within three months.


2. The owner should inspect the dam for seepage during the refilling operation.

d. O & M Procedures

The owner should develop, within one (1) year after formal approval of the report, written operating procedures and a periodic maintenance plan to insure the safety of the dam.



P L A T E S

**ELECTRIC LIGHT POND DAM
BORO OF PARK RIDGE
BERGEN COUNTY, N. J.**




KEY MAP

PLATE I



VICINITY MAP

PLATE IA




LEGEND

TRIASSIC

Rb Brunswick Formation
Soft Red Shale with Interbeds of Red Sandstone

NOTE: Glacial - Fluvial Sands and Gravels Mantling
Bedrock in Pascack Brook Valley not Shown

GEOLOGIC MAP ELECTRIC LIGHT POND DAM



2



GENERAL PLAN

FOR THE RECONSTRUCTION OF DULLES

AND THE RECONSTRUCTION OF THE

WASHINGTON METRO AREA

AND THE RECONSTRUCTION OF THE

WASHINGTON METRO AREA

PLATE 3

1

HOUSE

25-37 50-14-00

25-37 50-14-00

25-37 50-14-00

25-37 50-14-00

VERTICAL TEMPERATURE

1920

1920

GENERAL PROFILE
FOR THE REPAIR AND RECONSTRUCTION OF DAM
ELECTRIC LIGHT POND

BOROUGH OF PARK RIDGE
BOROUGH OF NEW JERSEY
DATE 1920


1

LEGEND
PRESENT CONTOURS
PROPOSED FOR CONTINUING CONTOUR

PROPOSED

PROPOSED

PROPOSED



PLAN
EAST SPILLWAY AND EMERGENCY SPILLWAY
ELECTRIC LIGHT POND
BOROUGH OF PARK RIDGE
NEW YORK
JULY 1910
BY J. B. HARRIS
ENGINEER

SECTION OF PAVEMENT
SHOWING EXPANSION JOINT
EMERGENCY SPILLWAY
SCALE 1-1-6



ELEVATION
SCALE 4-10




SECTION D-D
SCALE 1/4"=1'-0"

SECTION A-A


J

Sheet 6 of 6
 ELEVATION AND SECTIONS

4Y



TYPICAL SECTION
 EARTH DAM
 SCALE 1/2" = 1'-0"



SECTION
 EMERGENCY SPILLWAY
 SCALE 1/2" = 1'-0"


FILE

ELEVATION AND SECTIONS
 EAST SPILLWAY AND EMERGENCY SPILLWAY
 ELECTRIC LIGHT POND
 BOROUGH OF PARK RIDGE
 BERK COUNTY, N.J.


SECTION A-A
 SCALE 1/2" = 1'-0"

ROBERT ALBERTI & SONS
 ENGINEERS
 NEW YORK, N.Y.



1



PLAN
SCALE 1/4" = 1'-0"




ELEVATION
SCALE 1/4" = 1'-0"



FILE

WEST SPILLWAY
ELECTRIC LIGHT POND
BOROUGH OF PARK RIDGE
VIRGINIA COUNTY

1




WEST SECTION
12th Street
1907



EAST SECTION
12th Street
1907

2



MIDDLE SECTION

WEST 1/4 1912

1912 21/200




WEST 1/4 1912



1912 21/200

SECTION OF THE ROCK LAYER
WEST 1/4 1912
1912 21/200
SECTION OF THE ROCK LAYER
WEST 1/4 1912
1912 21/200

The image displays four stratigraphic columns, labeled 1, 2, 3, and 4, representing geological profiles. Each column includes a vertical scale of elevations and corresponding soil or rock descriptions.

- Column 1:**
 - Ground Surface: El. 185
 - Scale: 11 to 39
 - Descriptions: Sand & gravel, Red sand, gravel, & clay, Sand & gravel, Boulders, Clay & gravel, Boulders, Soft sandy rock, Rock.
- Column 2:**
 - Ground Surface: El. 184.5
 - Scale: 1 to 40
 - Descriptions: Sand & gravel, Red clay & gravel, Boulder, Red clay & gravel, Soft red shale & clay, Sandstone.
- Column 3:**
 - Ground Surface: El. 184.5
 - Scale: 1 to 41
 - Descriptions: Sand & gravel, Clay, gravel & shale, Sandstone, Sandstone, shale & clay, Sandstone.
- Column 4:**
 - Ground Surface: El. 184.5
 - Scale: 1 to 26
 - Descriptions: Sand & gravel, Red clay & gravel, Red clay & gravel, Sandstone.





PROPOSED PARK RIDGE DAM
TEST BORING DATA
BOROUGH OF PARK RIDGE, N J
HARLEY & GARLICK, ENGINEERS
FAIRLAWN, N J.

RILEY ENGINEERING & DRILLING CO.
1733 EAST 31ST ST., BROOKLYN 10

DATE: DEC 5, 1946

Thomas J. Riley
GENERAL MANAGER

1

Mill Road

112-13180

112-13180

112-13180

Proposed

112-13180

112-13180

112-13180



112-13180

112-13180

112-13180

Proposed Earth Dam

Top Existing Wall
Proposed First Spillway



1-12-50
1-12-50
1-12-50
1-12-50

1011
Spillway

2

PROFILE AND TEST BORING
PROPOSED DRAINAGE
BORING TO LEAK DETECT
WATER SOURCE

1011
1012
1013

1014

1015
1016
1017

PLATE 10

APPENDIX A

CHECK LIST - VISUAL OBSERVATIONS

CHECK LIST - ENGINEERING, CONSTRUCTION
MAINTENANCE DATA

CHECK LIST
VISUAL INSPECTION

PHASE 1

Name Dam ELECTRIC LIGHT POND County Bergen State New Jersey Coordinators NJ-DEP
(AKA MILL POND DAM &
SILVER LAKE)

Date(s) Inspection November 12, 1979 Weather Cloudy Temperature 50°F
December 3, 1979

Pool Elevation at Time of Inspection * NGVD
* Water in reservoir was drained for
current dredging operations. Tailwater at Time of Inspection 116.5 NGVD

Inspection Personnel:

November 12, 1979:

Chuck Chin
Henry King
Thomas Lakovich

December 3, 1979:

Eugene Koo
James McCormick

Owner/Representative:

November 12 and December 3, 1979

Charles E. Gasior, Borough Administrator
Borough Administrator
Borough of Park Ridge
Park Ridge, NJ 05656

CONCRETE SPILLWAYS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SEEPAGE OR LEAKAGE	None noticed. Water in reservoir drained for current dry dredging operations.	Inspect for seepage during the refilling operation.
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Severe spalling at left interface and at two buttresses at the west spillway. Minor spalling was noticed at the right interface of the west spillway. Severe spalling and a horizontal crack were noted on the right abutment of the east spillway.	Repair spalling and crack.
DRAINS	Yes-low level outlet drains-see "OUTLET WORKS".	
WATER PASSAGES	Yes-low level outlet-see "OUTLET DRAINS".	
FOUNDATIONS	Unknown	

CONCRETE SPILLWAYS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Concrete slabs show cracks along emergency spillway, numerous trees growing in these cracks. A longitudinal crack exists across the east spillway.	Remove trees and repair cracks.
STRUCTURAL CRACKING	None visible	
VERTICAL & HORIZONTAL ALIGNMENT	Good	
MONOLITH JOINTS	Good	
CONSTRUCTION JOINTS	Vegetation growing in construction joints at emergency spillway.	Remove vegetation.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SURFACE CRACKS None Noticed.		
	UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE No visible movement or cracking at or beyond toe was observed.	
	SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES No sloughing or erosion was visible.	
	VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST Good.	
RIPRAP FAILURES N/A		

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
	<p>Numerous Trees, small and medium sized, growing on top of and on both sides of earth embankment and on the emergency spillway. Concrete Core, one foot wide, visible on top of embankment for a distance of 94 feet from west spillway. Steel Sheeting visible for distance of 21 feet from the emergency spillway.</p>	<p>Remove trees.</p>
	<p>JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM Minor erosion behind left abutment of west spillway</p>	
	<p>ANY NOTICEABLE SEEPAGE None noticed. Water in reservoir drained for current dry dredging operations.</p>	
	<p>STAFF GAGE AND RECORDER None</p>	
	<p>DRAINS None</p>	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CRACKING & SPALLING OF CONCRETE SURFACES IN STILLING BASIN	None visible.	
INTAKE STRUCTURE	A four feet diameter concrete sluice way, with trash rack, exists at the east base of abandoned powerhouse west of west spillway. Trash rack has one bar missing and some bars are damaged. A four feet diameter concrete sluice way exists at the base of east spillway. Both sluice ways in good condition.	Repair trash rack.
OUTLET STRUCTURE	Water exits from the four feet diameter concrete sluice way at west way at west base of east spillway on to a concrete apron.	
OUTLET FACILITIES	The rising stem sluice gate at the west sluice was inoperable. The concrete foundation supporting the valve stem was deteriorated. Water from pump house mentioned above exits through two concrete notches (3'± x 2'± & 5' ± x 3'±) at south base of pump house into channel.	Replace valve. Repair stem stand concrete support.
EMERGENCY GATE	Emergency spillway adjacent to east spillway.	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONCRETE WEIR See "Concrete Spillways"		
APPROACH CHANNEL Reservoir-water in reservoir was drained for current dry dredging operations.		
DISCHARGE CHANNEL Two in good condition.		
BRIDGE AND PIERS None		

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONCRETE SILL N/A		
APPROACH CHANNEL N/A		
DISCHARGE CHANNEL N/A		
BRIDGE AND PIERS N/A		
GATES & OPERATION EQUIPMENT N/A		

INSTRUMENTATION		REMARKS AND RECOMMENDATIONS
VISUAL EXAMINATION OF MONUMENTATION/SURVEYS None	OBSERVATIONS	
OBSERVATION WELLS None		
WEIRS None		
PIEZOMETERS None		
OTHER None		

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
SLOPES	Water in reservoir was drained for current dry dredging operations. Moderate side slopes, no indication of slope instability	
SEDIMENTATION	Reservoir is currently being dredged.	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS AND RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.) Condition of both channels good. A roadway bridge crosses over east channel approximately 700 feet from the east spillway.		
SLOPES 2 horizontal to 1 vertical.		
APPROXIMATE NUMBER OF HOMES AND POPULATION A municipal building (Borough of Park Ridge), a recreation area and a lumber yard approximately 1200 feet from east spillway.		

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	Available on microfilm at NJ Department of Environmental Protection (NJ-DEP), 1474 Prospect Street, P.O. Box CN-029 Trenton, NJ 08625
REGIONAL VICINITY MAP	Available--Bergen County Map and U.S.G.S. Quadrangle sheet for Park Ridge, New Jersey-New York
CONSTRUCTION HISTORY	No formal history exists, but it can be deduced from available plans and drawings
TYPICAL SECTIONS OF DAM	Available on microfilm at NJ-DEP
HYDROLOGIC/HYDRAULIC DATA	No hydrologic data. Hydraulic data available on microfilm at NJ-DEP
OUTLETS - PLAN	Available on microfilm (NJ-DEP)
- DETAILS	Available in microfilm (NJ-DEP)
- CONSTRAINTS	None
- DISCHARGE RATINGS	Not available
RAINFALL / RESERVOIR RECORDS	Not available

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
(continued)

ITEM	REMARKS
DESIGN REPORTS	None available.
GEOLOGY REPORTS	Available. U.S.G.S. Geologic Overlay Sheet for Bergen County and Engineering Soil Survey of New Jersey, Report # 4--Bergen and Hudson Counties, by Rutgers University.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	} None available }
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None available Test boring data, dated 1946 & 1951, available on microfilm at NJ-DEP. None available None available
POST-CONSTRUCTION SURVEYS OF DAM	None
BORROW SOURCES	Unknown
SPILLWAY PLAN - SECTIONS) - DETAILS)	Available on microfilm at NJ-DEP

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
(continued)

ITEM	REMARKS
OPERATING EQUIPMENT PLANS AND DETAILS	None available
MONITORING SYSTEMS	None
MODIFICATIONS	Repair and reconstruction, 1952. Available on microfilm at NJ-DEP.
HIGH POOL RECORDS	Not kept
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	Inspection report for Borough of Park Ridge, Bergen County, NJ, 1978 by A.G. Lichtenstein, and Associates, Inc., Teaneck, NJ
PRIOR ACCIDENTS OF FAILURE OF DAM - DESCRIPTION - REPORTS	Available on microfilm at NJ-DEP, which states that failure occurred during July 23, 1945 flood.
MAINTENANCE OPERATION RECORDS	None known to exist

APPENDIX B

PHOTOGRAPHS

(Taken on December 3, 1979)

Note: Water in reservoir was drained for dry
dredging operations when photos were taken .

ELECTRIC LIGHT POND DAM



Photo 1 - View of West spillway from downstream. Abandoned power house is at left. Portion of earth embankment is at right.



Photo 2 - Detail showing spalling of the two buttresses, abutment and wingwall of West spillway. View is from downstream.

ELECTRIC LIGHT POND DAM



Photo 3 - View from reservoir side with dam and concrete core visible at left. The West spillway, adjacent to the abandoned power house, can be seen in center.



Photo 4 - View of retaining wall at right side of West spillway and base of abandoned tower. Note vertical crack and spalling.

ELECTRIC LIGHT POND DAM



Photo 5 - View of West spillway with reservoir on right. Note sluice way, valve and base of abandoned power house at top.




Photo 6 - Detail of sluice way at reservoir side of West spillway. Note missing bar from trash rack.

ELECTRIC LIGHT POND DAM



Photo 7 - View of the East spillway from reservoir side.
Note horizontal crack and spalling of right
abutment.



Photo 8 - View of reservoir from East spillway showing current
dredging operations.

ELECTRIC LIGHT POND DAM

Photo 9 - Detail showing spalling, exposed rebar and crack in right abutment of East spillway. Portion of emergency spillway is shown at right.



Photo 10 - Detail showing vertical crack in left abutment of East spillway and the crack across spillway.

ELECTRIC LIGHT POND DAM



Photo 11 - View of downstream channel from West spillway
(at bottom).




Photo 12 - View of East downstream channel. Sluice way water from
under East spillway is shown at left and portion
of emergency spillway at right.

ELECTRIC LIGHT POND DAM



Photo 13 - View of East channel, looking downstream, showing roadway bridge approximately 700 feet from the East spillway.



Photo 14 - View, looking upstream, of East and West channels merging approximately 800 feet from the East spillway. East channel is on right.

ELECTRIC LIGHT POND DAM



Photo 15 - View, looking upstream, toward East spillway on right center and portion of emergency spillway adjacent to it, on the left. Note sluiceway under East spillway. Embankment and West spillway is out of photo on viewer's left.

APPENDIX C

SUMMARY OF ENGINEERING DATA

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

Name of Dam: ELECTRIC LIGHT POND DAM

Drainage Area Characteristics: 14.2 square miles

Elevation Top Normal Pool (Storage Capacity): 132.0 NGVD (18 acre-ft.)

Elevation Top Flood Control Pool (Storage Capacity): N/A

Elevation Maximum Design Pool: 137.84 NGVD (SDF pool: 65 acre-feet)

Elevation Top Dam: 137.60 NGVD (63 acre-feet)

SPILLWAY CREST:

- a. Elevation 132.0 for east and west, 134.5 for emergency
- b. Type Ungraded concrete ogee for East & West, trapezoidal weir for emergency
- c. Width 9 ft. (east); 6 ft. (west); 12 ft. (emergency)
- d. Length 20 ft. (east), 47 ft. (west), 66 ft. (emergency)
- e. Location Spillover Not observed due to drain flow from low level pipes
Water in reservoir drained for dry dredging
- f. No. and Type of Gates None

OUTLET WORKS:

- a. Type 2-48-inch diameter low level outlet
- b. Location One located on the west of west spillway through power-house and other located at the west of east spillway
- c. Entrance Inverts 124.3 ft. (NGVD, west) 122.45 (NGVD, east)
- d. Exit Inverts 122.3 NGVD (Estimated-opening from power house)
122.07(NGVD East)
- e. Emergency Draindown Facilities 2-48-inch pipe with manual operated gate valves


HYDROMETEOROLOGICAL GAGES:

- a. Type None
- b. Location None
- c. Records None

MAXIMUM NON-DAMAGING DISCHARGE: 4,634 cfs @ 137.6 NGVD

APPENDIX D

HYDROLOGIC COMPUTATIONS



Scale 1" = 1 Mile
ELECTRIC LIGHT POND DAM
DRAINAGE BASIN

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NJ DAM INSP. GROUP III
ELECTRIC LIGHT DAM
COMPUTED BY EKO CHECKED BY C.L.C.

SHEET NO. 1 OF 12
JOB NO. 15-AFE-01
DATE 12/4/79

SIZE CLASSIFICATION

SURFACE AREA OF MAIN IMPOUNDMENT

7 ACRES

AVERAGE DEPTH

9 FT ±

STRUCTURAL HEIGHT OF DAM

20.6 FT

SIZE CLASSIFICATION

Small

Hazard Potential Classification

Behind recreation park & police range but
1/2 OF THE DAM

Hazard potential classification

Minor

Recommended SDF

1/2 PMF

HYDROLOGIC ANALYSIS

THE HEC-1 DB WILL BE USED TO ROUTE THE

DATA USING Snyder Method

$$C_e = 4.3 \quad 640 C_p = 330$$

(supplied by G. Sault US Army Corps of Engineers)

$$D.A. = 14.252 \text{ MF}$$

PRECIPITATION

From Fig. 15. ZONE 1 (REF Design of Small Dam 1977)

Probable flood precipitation = 25 inches for 6 hrs

Duration and 14.2 sq mi area

Duration (hrs)	Zone 1	Zone 6	Average	Value are reduced by 19.5% to
6	96	97	96.5	Discom + Cor
12	107	106	106.5	Miscalculation of Storm
24	116.5	114	115.3	Storm Intensity
48	121.0	123	123.5	

UNIT HYDROGRAPH

$$C_p = \frac{530}{640} = 0.83$$

$$t_p = C_t (LLC)^{0.3}$$

$$= 4.3 (9.12 \times 5.05)^{0.3} = 13.57 \text{ hrs}$$

INFILTRATION DATA

LAND USE $\frac{1}{2}$ Urban $\frac{1}{2}$ Woodlands

USE INITIAL INFILTRATION 1.5 inch
CONSTANT INFILTRATION 0.15 in/hr

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT N.J. DAM INSPECTION GROUP XVII
ELECTRIC LIGHT Pond
COMPUTED BY B.K.O. CHECKED BY C.L.C.

SHEET NO. 3 OF 12
JOB NO. 14-611-01
DATE 12/6/79



L = length of stream = 1.12 mile
 L_c = the stream length from
the outflow at Dam site
to a point approx. to the
center of gravity of
the river basin

Scale 1" = 1 mile

ELECTRIC LIGHT Pond Dam
DRAINAGE BASIN

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NJ DAM INSPECTION GROUP VI
ELECTRIC PUMP PILE
COMPUTED BY E. Koo CHECKED BY C.L.C.

SHEET NO. 4 OF 12
JOB NO. 12
DATE 12/6/79

ELEVATION - AREA - CAPACITY RELATIONSHIP

INFORMATION OBTAINED FROM DGS and General plan of Reconstruction

ELE	124.2*	132.0	137.6	140.	150
SURFACE AREA (AC)	0	7.0	2	17.5	50.9

* WEIGHTED ELE. OF BOTTOM OF LAKE AT SPILLWAY

HEC-1 DB PROGRAM WILL BE USED TO COMPUTE CAPACITY FROM SURFACE AREA AND ELEVATIONS.


Low Level Outlets

Electric Lake Pond was designed with 2 sluice gates controlled 4' ϕ concrete pipes low level outlet. Two pipes which are located through the crest spillway and all in to the power house are presently being used for draining the pond while designing operation lake pond.

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NJ DAM INSP GROUP XVII
ELECTRIC LIGHT POND
COMPUTED BY E.L.C. CHECKED BY C.L.C.

SHEET No. 5 of 12
JOB No. 12-431-1
DATE 12/6/50




ELEV	H ₁	H ₂	H ₃	H ₄	L ₁	L ₂	L ₃	L ₄	C ₁	C ₂	C ₃	C ₄	Σ	Σ
132.														
134.5	2.5				67				3.8				1006	
136	4.0	1.5			67				3.8	3.5			2037 + 424	= 2461
137.5	5.6	3.1			67				3.8	3.5			3374 + 1260	= 4634
139.0	7.0	4.5	1.4		67		410		3.8	3.5	3.75		4715 + 2200 + 2272	= 9187
140.0	8	5.5	2.4		67		420		3.8	3.5	3.75		5761 + 2960 + 510	= 13751
150.0	14.0	15.5	12.4	1.7			100		3.8	3.5	3.75		19493 + 14000 + 1830 + 1000	= 122409

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NEW DAM AND GROUP VII
ELECTRIC LIGHT POND
COMPUTED BY B.K. CHECKED BY C.L.C.


SHEET NO. 6 OF 12
JOB NO. 12-13-01
DATE 12/16/79



FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NO. 1 INSP GROUP 211.
Electric Line Ford
COMPUTED BY RIC CHECKED BY CLC

SHEET NO. 7 OF 12
JOB NO. 10-A93-01
DATE 12/7/79



Overtopping of Dam occurs at Ele. 137.6 with
 $Q = 4845$ CFS ($\sim 45\%$ PMF)

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NJ Dam Insp. Group VIII
ELECTRIC MOUNT POND
COMPUTED BY BK

CHECKED BY C.L.C.

SHEET NO. 8 OF 12
JOB NO. 10-A-3-1
DATE 2/11/80

Sensitivity Analysis summary

Bridge width	side slope	Preach bottom elev.	Fail time hr	Initial water surface	Fail elev.	Max. Peak
40	1	126	0.5	132	137.17	5490
40	1	126	0.5	132	137.84	6381 ←
40	1	126	0.5	132	137.80	6330
40	1	126	0.5	132	137.75	6260



FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NIDAM INSIDE GROUP VII
ELECTRIC LIGHT POOL
COMPUTED BY E.K. CHECKED BY C.H.C.

SHEET NO. 9 OF 12
JOB NO. 10-55-01
DATE 12/7/79

BREACH ANALYSIS

Based on Sensitivity Analysis, the breach begins to develop when the lake stage to reach elevation 137.02 with max. peak outflow 60.24 ft³/sec. than the top of dam.



SECTION 1

FREDERIC R. HARRIS, INC.

CONSULTING ENGINEERS

SUBJECT Adam Lind Group VII

ELECTRIC LIGHT OIL


COMPUTED BY BK

CHECKED BY CLC

SHEET NO. 10 OF 12

Job No. 10-15' 3-01

DATE 2/15/80



Cross - Section


End of Patch 1 Sbt. 1)

$$\zeta = 0.0083$$

FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT NT Dam Safety Insp. Rep. Group 5/1
Electric Light Pond
COMPUTED BY EK CHECKED BY CLC

SHEET NO. 11 OF 12
JOB NO. 10-A55-1
DATE 2/19/80




FREDERIC R. HARRIS, INC.
CONSULTING ENGINEERS

SUBJECT WATER MAIN
ELECTRIC MOUNT
COMPUTED BY E.K. CHECKED BY C.L.C.

SHEET NO. 12 OF 12
JOB NO. 2
DATE 12/16/79

Drawdown Time computation



Normal Elevation TO
STAKE 132.0
DA = 14.2 sq ft
INFLOW = 2.5 cfs
= 2.5 x 4.05
Use Fig B-115 of
Design of Small dams
for Q AVE. water
discharge

For simplification Assume we have a drawdown curve of 129.5 + 121.3 / 2 = 122.2
not a true average drawdown curve.

RES ELE	WATER SURF	AVE AREA AC.	VOLUME FT-3	AVE H RES ELE	Q AVE outlet DISCHARGE	t, hrs Time to drain Vol x 2.4 1.98 x Q	Calculated Time hrs	Time to drain 2.4 in 2.4 in	Time to drain 2.4 in
132	7.8	5.44	10.88	131	2.2	340	0.39	0.39	0.42
131	3.87	2.77	5.54	129	1.7	280	0.29	0.33	0.63
129	1.66	1.02	2.04	127	1.2	200	0.12	0.75	0.82
126	0.37	0.22	0.44	125.5	0.83	120	0.04	0.79	0.7
125	0.07	0.04	0.1	125.1	0.73	96	0.01	0.80	0.88
124.2	0			123.2					
122.2	0								

TIME OF COMPLETE DRAWDOWN WITH NO INFLOW = 0.80 hr.

TIME OF COMPLETE DRAWDOWN WITH INFLOW = 0.88 hr

$$\left(\text{ASSUME } A_1 = \frac{A_2}{\left(\frac{h}{H_T} + 1 \right)^2} \quad A_2 = 7 \text{ Acres} \quad h + H_T = 7.8 \right)$$

N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10A8301
 N J 00245 ELECTRIC LIGHT POND, BERGEN COUNTY, NJ
 MULT RATIO ROUTING, PRC-HARRIS INC., WOODBRIDGE, N J

A1	0	30	0	0	0	1
A2	150					
A3	5					
B1	2	1				
J1	5	4	3	2	1	
N1	0					
K1						
M1	1					
P1						
T1						
W1	13.6	0.83				
X1	-1	-05	2			
K1	1	DAME				
Y1						
Y1	1					
Y4	132	134.5	136	137.6	139	140
Y5	0	1006	2461	4634	9152	13751
Y6	0	7	9	17.5	57.9	102409
Y7	122.0	132	137.6	140	150	
Y8	132					
Y9	137.6					
Y10	40	1	126	0.5	132	137.87
Y11	40	1	126	0.5	132	200
Y12	1	REACH				
Y13	1	U/S OF PARK AVE., PARK RINGE, N J				
Y14	1					
Y15	0.1	0.05	0.1	109	130	1100
Y16	650	130	950	120	1268	115
Y17	1332	115	1550	120	1620	130
Y18	99					
Y19						
Y20						
Y21						
Y22						
Y23						
Y24						
Y25						
Y26						
Y27						
Y28						
Y29						
Y30						
Y31						
Y32						
Y33						
Y34						
Y35						
Y36						
Y37						
Y38						
Y39						
Y40						
Y41						
Y42						
Y43						
Y44						
Y45						
Y46						
Y47						
Y48						
Y49						
Y50						
Y51						
Y52						
Y53						
Y54						
Y55						
Y56						
Y57						
Y58						
Y59						
Y60						
Y61						
Y62						
Y63						
Y64						
Y65						
Y66						
Y67						
Y68						
Y69						
Y70						
Y71						
Y72						
Y73						
Y74						
Y75						
Y76						
Y77						
Y78						
Y79						
Y80						
Y81						
Y82						
Y83						
Y84						
Y85						
Y86						
Y87						
Y88						
Y89						
Y90						
Y91						
Y92						
Y93						
Y94						
Y95						
Y96						
Y97						
Y98						
Y99						
Y100						

109

1320

109

0.0083

115

1280

130

109

1320

109

1320

109

1320

AD-A087 329


NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/13
NATIONAL DAM SAFETY PROGRAM, ELECTRIC LIGHT POND DAM (NJ00245),--ETC(U)
FEB 80 J TALERICO DACW61-79-C-0011

UNCLASSIFIED

2 of 2
PAGE 1 OF 1

NI

END
DATE
FILMED
9-80
DTIC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10A8301
 N J 00245 ELECTRIC LIGHT POND, BERGEN COUNTY, NJ
 MULT RATIO ROUTING,PRC-HARRIS INC., WOODBRIDGE, N J

JOB SPECIFICATION									
NO	MHR	NMIN	1DAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
150	0	30	0	0	0	0	0	1	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 2 NRTIO= 1 LRTIO= 1

RTIOS= .50

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH THROUGH ELECTRIC LIGHT POND

ISTAD	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
LAKE	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INHYD	IUNB	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	14.20	0.00	14.20	.81	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	25.00	96.50	106.50	115.30	123.50	0.00	0.00

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CHSTL	ALSNX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.50	15	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 13.60 CP= .83 NTA= 0

RECESSION DATA

CLARK DID NOT CONVERGE TO GIVEN SNYDER COEFFICIENTS
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC=38.47 AND R= 8.85 INTERVALS

STRTQ= -1.00 ORCSN= -.05 RTIOR= 2.00

UNIT HYDROGRAPH 71 END-OF-PERIOD ORDINATES, LAB= 13.46 HOURS, CP= .82 VOL= 1.00									
6.	22.	44.	69.	97.	126.	155.	185.	215.	244.
274.	303.	331.	359.	387.	413.	440.	465.	490.	514.
534.	549.	561.	570.	575.	578.	577.	574.	569.	562.
552.	540.	526.	510.	491.	470.	445.	415.	378.	338.
302.	270.	242.	216.	194.	173.	155.	139.	124.	111.
99.	89.	79.	71.	63.	57.	51.	45.	41.	36.
33.	29.	26.	23.	21.	19.	17.	15.	13.	12.

END-OF-PERIOD FLOW

0

MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	1.01	30	1	00	00	13	1.02	14.00	76	1.17	1.09	08	418.
1.01	1.01	1.00	2	00	00	12	1.02	14.30	77	1.46	1.38	08	547.
1.01	1.01	1.30	3	00	00	12	1.02	15.00	78	1.46	1.38	08	710.
1.01	1.01	2.00	4	00	00	11	1.02	15.30	79	1.77	1.70	08	914.
1.01	1.01	2.30	5	00	00	10	1.02	16.00	80	5.61	5.53	08	1183.
1.01	1.01	3.00	6	00	00	9	1.02	16.30	81	1.36	1.28	08	1536.
1.01	1.01	3.30	7	00	00	9	1.02	17.00	82	1.36	1.28	08	1953.
1.01	1.01	4.00	8	00	00	8	1.02	17.30	83	1.07	09	08	2420.
1.01	1.01	4.30	9	00	00	8	1.02	18.00	84	1.07	09	08	2928.
1.01	1.01	5.00	10	00	00	7	1.02	18.30	85	09	01	08	3464.
1.01	1.01	5.30	11	00	00	7	1.02	19.00	86	09	01	08	4014.
1.01	1.01	6.00	12	00	00	6	1.02	19.30	87	09	01	08	4569.
1.01	1.01	6.30	13	01	01	6	1.02	20.00	88	09	01	08	5123.
1.01	1.01	7.00	14	01	01	5	1.02	20.30	89	09	01	08	5673.
1.01	1.01	7.30	15	01	01	5	1.02	21.00	90	09	01	08	6214.
1.01	1.01	8.00	16	01	01	5	1.02	21.30	91	09	01	08	6746.
1.01	1.01	8.30	17	01	01	4	1.02	22.00	92	09	01	08	7265.
1.01	1.01	9.00	18	01	01	4	1.02	22.30	93	09	01	08	7768.
1.01	1.01	9.30	19	01	01	4	1.02	23.00	94	09	01	08	8252.
1.01	1.01	10.00	20	01	01	4	1.02	23.30	95	09	01	08	8712.
1.01	1.01	10.30	21	01	01	3	1.03	0.00	96	09	01	08	9145.
1.01	1.01	11.00	22	01	01	3	1.03	3.30	97	00	00	00	9547.
1.01	1.01	11.30	23	01	01	3	1.03	1.00	98	00	00	00	9914.
1.01	1.01	12.00	24	01	01	3	1.03	1.30	99	00	00	00	10236.
1.01	1.01	12.30	25	07	07	3	1.03	2.00	100	00	00	00	10504.
1.01	1.01	13.00	26	07	07	2	1.03	2.30	101	00	00	00	10712.
1.01	1.01	13.30	27	08	08	2	1.03	3.00	102	00	00	00	10860.
1.01	1.01	14.00	28	08	08	2	1.03	3.30	103	00	00	00	10949.
1.01	1.01	14.30	29	10	10	2	1.03	4.00	104	00	00	00	10981.
1.01	1.01	15.00	30	10	10	2	1.03	4.30	105	00	00	00	10980.
1.01	1.01	15.30	31	13	13	2	1.03	5.00	106	00	00	00	10888.
1.01	1.01	16.00	32	40	40	2	1.03	5.30	107	00	00	00	10769.
1.01	1.01	16.30	33	10	10	1	1.03	6.00	108	00	00	00	10605.
1.01	1.01	17.00	34	10	10	1	1.03	6.30	109	00	00	00	10397.
1.01	1.01	17.30	35	08	08	1	1.03	7.00	110	00	00	00	10143.
1.01	1.01	18.00	36	08	08	1	1.03	7.30	111	00	00	00	9842.
1.01	1.01	18.30	37	01	01	1	1.03	8.00	112	00	00	00	9491.
1.01	1.01	19.00	38	01	01	1	1.03	8.30	113	00	00	00	9095.
1.01	1.01	19.30	39	01	01	1	1.03	9.00	114	00	00	00	8658.
1.01	1.01	20.00	40	01	01	1	1.03	9.30	115	00	00	00	8182.
1.01	1.01	20.30	41	01	01	1	1.03	10.00	116	00	00	00	7670.
1.01	1.01	21.00	42	01	01	1	1.03	10.30	117	00	00	00	7121.
1.01	1.01	21.30	43	01	01	1	1.03	11.00	118	00	00	00	6533.
1.01	1.01	22.00	44	01	01	1	1.03	11.30	119	00	00	00	5938.
1.01	1.01	22.30	45	01	01	1	1.03	12.00	120	00	00	00	5370.
1.01	1.01	23.00	46	01	01	1	1.03	12.30	121	00	00	00	4835.
1.01	1.01	23.30	47	01	01	1	1.03	13.00	122	00	00	00	4338.
1.02	1.02	0.00	48	01	01	1	1.03	13.30	123	00	00	00	3887.
1.02	1.02	30	49	06	06	1	1.03	14.00	124	00	00	00	3482.
1.02	1.02	1.00	50	06	06	1	1.03	14.30	125	00	00	00	3119.
1.02	1.02	1.30	51	06	06	1	1.03	15.00	126	00	00	00	2794.
1.02	1.02	2.00	52	06	06	1	1.03	15.30	127	00	00	00	2503.
1.02	1.02	2.30	53	06	06	1	1.03	16.00	128	00	00	00	2242.
1.02	1.02	3.00	54	06	06	1	1.03	16.30	129	00	00	00	2007.
1.02	1.02	3.30	55	06	06	1	1.03	17.00	130	00	00	00	1797.
1.02	1.02	4.00	56	06	06	1	1.03	17.30	131	00	00	00	1608.
1.02	1.02	4.30	57	06	06	1	1.03	18.00	132	00	00	00	1439.
1.02	1.02	5.00	58	06	06	1	1.03	18.30	133	00	00	00	1286.
1.02	1.02	5.30	59	06	06	1	1.03	19.00	134	00	00	00	1150.
1.02	1.02	6.00	60	06	06	1	1.03	19.30	135	00	00	00	1028.
1.02	1.02	6.30	61	17	09	1	1.03	20.00	136	00	00	00	918.
1.02	1.02	7.00	62	17	09	3	1.03	20.30	137	00	00	00	821.
1.02	1.02	7.30	63	17	09	7	1.03	21.00	138	00	00	00	733.
1.02	1.02	8.00	64	17	09	14	1.03	21.30	139	00	00	00	655.

PLAN 2

	ELEVATION STORAGE OUTFLOW	INITIAL VALUE 132.00 23. 0.	SPILLWAY CREST 132.00 23. 0.	TUP OF DAM 137.60 68 4634.	
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV				
.50	137.87	MAXIMUM DEPTH OVER DAM .27	MAXIMUM STORAGE AC-FT 71.	MAXIMUM OUTFLOW CFS 5490.	DURATION OVER TOP HOURS 8.00
					TIME OF MAX OUTFLOW HOURS 52.00
					TIME OF FAILURE HOURS 0.00
</					

N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10A8301
 N J 00245 ELECTRIC LIGHT POND, BERGEN COUNTY, NJ
 MULT RATIO ROUTING.PRC-HARRIS INC., WOODBRIDGE, N J

A1
 A2
 A3

B
 B1
 B2
 B3
 B4
 B5
 B6
 B7
 B8
 B9
 B10
 B11
 B12
 B13
 B14
 B15
 B16
 B17
 B18
 B19
 B20
 B21
 B22
 B23
 B24
 B25
 B26
 B27
 B28
 B29
 B30
 B31
 B32
 B33
 B34
 B35
 B36
 B37
 B38
 B39
 B40
 B41
 B42
 B43
 B44
 B45
 B46
 B47
 B48
 B49
 B50
 B51
 B52
 B53
 B54
 B55
 B56
 B57
 B58
 B59
 B60
 B61
 B62
 B63
 B64
 B65
 B66
 B67
 B68
 B69
 B70
 B71
 B72
 B73
 B74
 B75
 B76
 B77
 B78
 B79
 B80
 B81
 B82
 B83
 B84
 B85
 B86
 B87
 B88
 B89
 B90
 B91
 B92
 B93
 B94
 B95
 B96
 B97
 B98
 B99
 B100

C
 C1
 C2
 C3
 C4
 C5
 C6
 C7
 C8
 C9
 C10
 C11
 C12
 C13
 C14
 C15
 C16
 C17
 C18
 C19
 C20
 C21
 C22
 C23
 C24
 C25
 C26
 C27
 C28
 C29
 C30
 C31
 C32
 C33
 C34
 C35
 C36
 C37
 C38
 C39
 C40
 C41
 C42
 C43
 C44
 C45
 C46
 C47
 C48
 C49
 C50
 C51
 C52
 C53
 C54
 C55
 C56
 C57
 C58
 C59
 C60
 C61
 C62
 C63
 C64
 C65
 C66
 C67
 C68
 C69
 C70
 C71
 C72
 C73
 C74
 C75
 C76
 C77
 C78
 C79
 C80
 C81
 C82
 C83
 C84
 C85
 C86
 C87
 C88
 C89
 C90
 C91
 C92
 C93
 C94
 C95
 C96
 C97
 C98
 C99
 C100

D
 D1
 D2
 D3
 D4
 D5
 D6
 D7
 D8
 D9
 D10
 D11
 D12
 D13
 D14
 D15
 D16
 D17
 D18
 D19
 D20
 D21
 D22
 D23
 D24
 D25
 D26
 D27
 D28
 D29
 D30
 D31
 D32
 D33
 D34
 D35
 D36
 D37
 D38
 D39
 D40
 D41
 D42
 D43
 D44
 D45
 D46
 D47
 D48
 D49
 D50
 D51
 D52
 D53
 D54
 D55
 D56
 D57
 D58
 D59
 D60
 D61
 D62
 D63
 D64
 D65
 D66
 D67
 D68
 D69
 D70
 D71
 D72
 D73
 D74
 D75
 D76
 D77
 D78
 D79
 D80
 D81
 D82
 D83
 D84
 D85
 D86
 D87
 D88
 D89
 D90
 D91
 D92
 D93
 D94
 D95
 D96
 D97
 D98
 D99
 D100

E
 E1
 E2
 E3
 E4
 E5
 E6
 E7
 E8
 E9
 E10
 E11
 E12
 E13
 E14
 E15
 E16
 E17
 E18
 E19
 E20
 E21
 E22
 E23
 E24
 E25
 E26
 E27
 E28
 E29
 E30
 E31
 E32
 E33
 E34
 E35
 E36
 E37
 E38
 E39
 E40
 E41
 E42
 E43
 E44
 E45
 E46
 E47
 E48
 E49
 E50
 E51
 E52
 E53
 E54
 E55
 E56
 E57
 E58
 E59
 E60
 E61
 E62
 E63
 E64
 E65
 E66
 E67
 E68
 E69
 E70
 E71
 E72
 E73
 E74
 E75
 E76
 E77
 E78
 E79
 E80
 E81
 E82
 E83
 E84
 E85
 E86
 E87
 E88
 E89
 E90
 E91
 E92
 E93
 E94
 E95
 E96
 E97
 E98
 E99
 E100

F
 F1
 F2
 F3
 F4
 F5
 F6
 F7
 F8
 F9
 F10
 F11
 F12
 F13
 F14
 F15
 F16
 F17
 F18
 F19
 F20
 F21
 F22
 F23
 F24
 F25
 F26
 F27
 F28
 F29
 F30
 F31
 F32
 F33
 F34
 F35
 F36
 F37
 F38
 F39
 F40
 F41
 F42
 F43
 F44
 F45
 F46
 F47
 F48
 F49
 F50
 F51
 F52
 F53
 F54
 F55
 F56
 F57
 F58
 F59
 F60
 F61
 F62
 F63
 F64
 F65
 F66
 F67
 F68
 F69
 F70
 F71
 F72
 F73
 F74
 F75
 F76
 F77
 F78
 F79
 F80
 F81
 F82
 F83
 F84
 F85
 F86
 F87
 F88
 F89
 F90
 F91
 F92
 F93
 F94
 F95
 F96
 F97
 F98
 F99
 F100

G
 G1
 G2
 G3
 G4
 G5
 G6
 G7
 G8
 G9
 G10
 G11
 G12
 G13
 G14
 G15
 G16
 G17
 G18
 G19
 G20
 G21
 G22
 G23
 G24
 G25
 G26
 G27
 G28
 G29
 G30
 G31
 G32
 G33
 G34
 G35
 G36
 G37
 G38
 G39
 G40
 G41
 G42
 G43
 G44
 G45
 G46
 G47
 G48
 G49
 G50
 G51
 G52
 G53
 G54
 G55
 G56
 G57
 G58
 G59
 G60
 G61
 G62
 G63
 G64
 G65
 G66
 G67
 G68
 G69
 G70
 G71
 G72
 G73
 G74
 G75
 G76
 G77
 G78
 G79
 G80
 G81
 G82
 G83
 G84
 G85
 G86
 G87
 G88
 G89
 G90
 G91
 G92
 G93
 G94
 G95
 G96
 G97
 G98
 G99
 G100

H
 H1
 H2
 H3
 H4
 H5
 H6
 H7
 H8
 H9
 H10
 H11
 H12
 H13
 H14
 H15
 H16
 H17
 H18
 H19
 H20
 H21
 H22
 H23
 H24
 H25
 H26
 H27
 H28
 H29
 H30
 H31
 H32
 H33
 H34
 H35
 H36
 H37
 H38
 H39
 H40
 H41
 H42
 H43
 H44
 H45
 H46
 H47
 H48
 H49
 H50
 H51
 H52
 H53
 H54
 H55
 H56
 H57
 H58
 H59
 H60
 H61
 H62
 H63
 H64
 H65
 H66
 H67
 H68
 H69
 H70
 H71
 H72
 H73
 H74
 H75
 H76
 H77
 H78
 H79
 H80
 H81
 H82
 H83
 H84
 H85
 H86
 H87
 H88
 H89
 H90
 H91
 H92
 H93
 H94
 H95
 H96
 H97
 H98
 H99
 H100

I
 I1
 I2
 I3
 I4
 I5
 I6
 I7
 I8
 I9
 I10
 I11
 I12
 I13
 I14
 I15
 I16
 I17
 I18
 I19
 I20
 I21
 I22
 I23
 I24
 I25
 I26
 I27
 I28
 I29
 I30
 I31
 I32
 I33
 I34
 I35
 I36
 I37
 I38
 I39
 I40
 I41
 I42
 I43
 I44
 I45
 I46
 I47
 I48
 I49
 I50
 I51
 I52
 I53
 I54
 I55
 I56
 I57
 I58
 I59
 I60
 I61
 I62
 I63
 I64
 I65
 I66
 I67
 I68
 I69
 I70
 I71
 I72
 I73
 I74
 I75
 I76
 I77
 I78
 I79
 I80
 I81
 I82
 I83
 I84
 I85
 I86
 I87
 I88
 I89
 I90
 I91
 I92
 I93
 I94
 I95
 I96
 I97
 I98
 I99
 I100

J
 J1
 J2
 J3
 J4
 J5
 J6
 J7
 J8
 J9
 J10
 J11
 J12
 J13
 J14
 J15
 J16
 J17
 J18
 J19
 J20
 J21
 J22
 J23
 J24
 J25
 J26
 J27
 J28
 J29
 J30
 J31
 J32
 J33
 J34
 J35
 J36
 J37
 J38
 J39
 J40
 J41
 J42
 J43
 J44
 J45
 J46
 J47
 J48
 J49
 J50
 J51
 J52
 J53
 J54
 J55
 J56
 J57
 J58
 J59
 J60
 J61
 J62
 J63
 J64
 J65
 J66
 J67
 J68
 J69
 J70
 J71
 J72
 J73
 J74
 J75
 J76
 J77
 J78
 J79
 J80
 J81
 J82
 J83
 J84
 J85
 J86
 J87
 J88
 J89
 J90
 J91
 J92
 J93
 J94
 J95
 J96
 J97
 J98
 J99
 J100

K
 K1
 K2
 K3
 K4
 K5
 K6
 K7
 K8
 K9
 K10
 K11
 K12
 K13
 K14
 K15
 K16
 K17
 K18
 K19
 K20
 K21
 K22
 K23
 K24
 K25
 K26
 K27
 K28
 K29
 K30
 K31
 K32
 K33
 K34
 K35
 K36
 K37
 K38
 K39
 K40
 K41
 K42
 K43
 K44
 K45
 K46
 K47
 K48
 K49
 K50
 K51
 K52
 K53
 K54
 K55
 K56
 K57
 K58
 K59
 K60
 K61
 K62
 K63
 K64
 K65
 K66
 K67
 K68
 K69
 K70
 K71
 K72
 K73
 K74
 K75
 K76
 K77
 K78
 K79
 K80
 K81
 K82
 K83
 K84
 K85
 K86
 K87
 K88
 K89
 K90
 K91
 K92
 K93
 K94
 K95
 K96
 K97
 K98
 K99
 K100

L
 L1
 L2
 L3
 L4
 L5
 L6
 L7
 L8
 L9
 L10
 L11
 L12
 L13
 L14
 L15
 L16
 L17
 L18
 L19
 L20
 L21
 L22
 L23
 L24
 L25
 L26
 L27
 L28
 L29
 L30
 L31
 L32
 L33
 L34
 L35
 L36
 L37
 L38
 L39
 L40
 L41
 L42
 L43
 L44
 L45
 L46
 L47
 L48
 L49
 L50
 L51
 L52
 L53
 L54
 L55
 L56
 L57
 L58
 L59
 L60
 L61
 L62
 L63
 L64
 L65
 L66
 L67
 L68
 L69
 L70
 L71
 L72
 L73
 L74
 L75
 L76
 L77
 L78
 L79
 L80
 L81
 L82
 L83
 L84
 L85
 L86
 L87
 L88
 L89
 L90
 L91
 L92
 L93
 L94
 L95
 L96
 L97
 L98
 L99
 L100

M
 M1
 M2
 M3
 M4
 M5
 M6
 M7
 M8
 M9
 M10
 M11
 M12
 M13
 M14
 M15
 M16
 M17
 M18
 M19
 M20
 M21
 M22
 M23
 M24
 M25
 M26
 M27
 M28
 M29
 M30
 M31
 M32
 M33
 M34
 M35
 M36
 M37
 M38
 M39
 M40
 M41
 M42
 M43
 M44
 M45
 M46
 M47
 M48
 M49
 M50
 M51
 M52
 M53
 M54
 M55
 M56
 M57
 M58
 M59
 M60
 M61
 M62
 M63
 M64
 M65
 M66
 M67
 M68
 M69
 M70
 M71
 M72
 M73
 M74
 M75
 M76
 M77
 M78
 M79
 M80
 M81
 M82
 M83
 M84
 M85
 M86
 M87
 M88
 M89
 M90
 M91
 M92
 M93
 M94
 M95
 M96
 M97
 M98
 M99
 M100

N
 N1
 N2
 N3
 N4
 N5
 N6
 N7
 N8
 N9
 N10
 N11
 N12
 N13
 N14
 N15
 N16
 N17
 N18
 N19
 N20
 N21
 N22
 N23
 N24
 N25
 N26
 N27
 N28
 N29
 N30
 N31
 N32
 N33
 N34
 N35
 N36
 N37
 N38
 N39
 N40
 N41
 N42
 N43
 N44
 N45
 N46
 N47
 N48
 N49
 N50
 N51
 N52
 N53
 N54
 N55
 N56
 N57
 N58
 N59
 N60
 N61
 N62
 N63
 N64
 N65
 N66
 N67
 N68
 N69
 N70
 N71
 N72
 N73
 N74
 N75
 N76
 N77
 N78
 N79
 N80
 N81
 N82
 N83
 N84
 N85
 N86
 N87
 N88
 N89
 N90
 N91
 N92
 N93
 N94
 N95
 N96
 N97
 N98
 N99
 N100

O
 O1
 O2
 O3
 O4
 O5
 O6
 O7
 O8
 O9
 O10
 O11
 O12
 O13
 O14
 O15
 O16
 O17
 O18
 O19
 O20
 O21
 O22
 O23
 O24
 O25
 O26
 O27
 O28
 O29
 O30
 O31
 O32
 O33
 O34
 O35
 O36
 O37
 O38
 O39
 O40
 O41
 O42
 O43
 O44
 O45
 O46
 O47
 O48
 O49
 O50
 O51
 O52
 O53
 O54
 O55
 O56
 O57
 O58
 O59
 O60
 O61
 O62
 O63
 O64
 O65
 O66
 O67
 O68
 O69
 O70
 O71
 O72
 O73
 O74
 O75
 O76
 O77
 O78
 O79
 O80
 O81
 O82
 O83
 O84
 O85
 O86
 O87
 O88
 O89
 O90
 O91
 O92
 O93
 O94
 O95
 O96
 O97
 O98
 O99
 O100

P
 P1
 P2
 P3
 P4
 P5
 P6
 P7
 P8
 P9
 P10
 P11
 P12
 P13
 P14
 P15
 P16
 P17
 P18
 P19
 P20
 P21
 P22
 P23
 P24
 P25
 P26
 P27
 P28
 P29
 P30
 P31
 P32
 P33
 P34
 P35
 P36
 P37
 P38
 P39
 P40
 P41
 P42
 P43
 P44
 P45
 P46
 P47
 P48
 P49
 P50
 P51
 P52
 P53
 P54
 P55
 P56
 P57
 P58
 P59
 P60
 P61
 P62
 P63
 P64
 P65
 P66
 P67
 P68
 P69
 P70
 P71
 P72
 P73
 P74
 P75
 P76
 P77
 P78
 P79
 P80
 P81
 P82
 P83
 P84
 P85
 P86
 P87
 P88
 P89
 P90
 P91
 P92
 P93
 P94
 P95
 P96
 P97
 P98
 P99
 P100

Q
 Q1
 Q2
 Q3
 Q4
 Q5
 Q6
 Q7
 Q8
 Q9
 Q10
 Q11
 Q12
 Q13
 Q14
 Q15
 Q16
 Q17
 Q18
 Q19
 Q20
 Q21
 Q22
 Q23
 Q24
 Q25
 Q26
 Q27
 Q28
 Q29
 Q30
 Q31
 Q32
 Q33
 Q34
 Q35
 Q36
 Q37
 Q38
 Q39
 Q40
 Q41
 Q42
 Q43
 Q44
 Q45
 Q46
 Q47
 Q48
 Q49
 Q50
 Q51
 Q52
 Q53
 Q54
 Q55
 Q56
 Q57
 Q58
 Q59
 Q60
 Q61
 Q62
 Q63
 Q64
 Q65
 Q66
 Q67
 Q68
 Q69
 Q70
 Q71
 Q72
 Q73
 Q74
 Q75
 Q76
 Q77
 Q78
 Q79
 Q80
 Q81
 Q82
 Q83
 Q84
 Q85
 Q86
 Q87
 Q88
 Q89
 Q90
 Q91
 Q92
 Q93
 Q94
 Q95
 Q96
 Q97
 Q98
 Q99
 Q100

R
 R1
 R2
 R3
 R4
 R5
 R6
 R7
 R8
 R9
 R10
 R11
 R12
 R13
 R14
 R15
 R16
 R17
 R18
 R19
 R20
 R21
 R22
 R23
 R24
 R25
 R26
 R27
 R28
 R29
 R30
 R31
 R32
 R33
 R34
 R35
 R36
 R37
 R38
 R39
 R40
 R41
 R42
 R43
 R44
 R45
 R46
 R47
 R48
 R49
 R50
 R51
 R52
 R53
 R54
 R55
 R56
 R57
 R58
 R59
 R60
 R61
 R62
 R63
 R64
 R65
 R66
 R67
 R68
 R69
 R70
 R71
 R72
 R73

N J DAM SAFETY INSPECTION PROGRAM---GROUP XVII 10A8301
 N J 00245 ELECTRIC LIGHT POND, BERGEN COUNTY, NJ
 MULT RATIO ROUTING.PRC-HARRIS INC., WOODBRIDGE, N.J

JOB SPECIFICATION									
NO	NH	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	INSTAN
150	0	30	0	0	0	0	0	1	0
			JOPER	NWT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 2 NRATIO= 1 LRTIO= 1

RTIOS= 50

***** ***** ***** ***** *****

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH THROUGH ELECTRIC LIGHT POND

ISTAD	ICOMP	IECON	ITAPE	JPLT	JFRT	INAME	ISTAGE	IAUTO
LAKE	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

IHYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	14.20	0.00	14.20	.81	0.000	0	1	0

PRECIP DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	25.00	96.50	106.50	115.30	123.50	0.00	0.00

LOSS DATA

LROPT	STNKR	DLTKR	RTIOL	ERAIN	STKRS	RTIOK	STRTL	CNSTL	ALSHX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.50	.15	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 13.60 CP= .83 NTA= 0

RECESSION DATA

STRIG= -1.00 GRCSN= -.05 RTIOR= 2.00

CLARK DID NOT CONVERGE TO GIVEN SNYDER COEFFICIENTS
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC=38.47 AND R= 8.85 INTERVALS

UNIT HYDROGRAPH 71 END-OF-PERIOD ORDINATES, LAG= 13.46 HOURS, CP= .82 VOL= 1.00									
6.	22.	44.	69.	97.	126.	155.	185.	215.	244.
274.	303.	331.	359.	387.	413.	440.	465.	490.	514.
534.	549.	561.	570.	575.	578.	577.	574.	569.	562.
552.	540.	526.	510.	491.	470.	445.	415.	378.	338.
302.	270.	242.	216.	194.	173.	155.	139.	124.	111.
99.	89.	79.	71.	63.	57.	51.	45.	41.	36.
33.	29.	26.	23.	21.	19.	17.	15.	13.	12.

END-OF-PERIOD FLOW

MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q
1.01	1.30	1	.00	0.00	.00	13	1.02	14.00	76	1.17	1.09	.00	410.
1.01	1.00	2	.00	0.00	.00	12	1.02	14.30	77	1.46	1.38	.08	547.
1.01	1.30	3	.00	0.00	.00	12	1.02	15.00	78	1.46	1.38	.08	710.
1.01	2.00	4	.00	0.00	.00	11	1.02	15.30	79	1.77	1.70	.08	914.
1.01	2.30	5	.00	0.00	.00	10	1.02	16.00	80	5.61	5.53	.08	1183.
1.01	3.00	6	.00	0.00	.00	9	1.02	16.30	81	1.36	1.28	.08	1536.
1.01	3.30	7	.00	0.00	.00	9	1.02	17.00	82	1.36	1.28	.08	1953.
1.01	4.00	8	.00	0.00	.00	8	1.02	17.30	83	1.07	.99	.08	2420.
1.01	4.30	9	.00	0.00	.00	8	1.02	18.00	84	1.07	.99	.08	2928.
1.01	5.00	10	.00	0.00	.00	7	1.02	18.30	85	.09	.01	.08	3464.
1.01	5.30	11	.00	0.00	.00	7	1.02	19.00	86	.09	.01	.08	4014.
1.01	6.00	12	.00	0.00	.00	6	1.02	19.30	87	.09	.01	.08	4569.
1.01	6.30	13	.01	0.00	.01	6	1.02	20.00	88	.09	.01	.08	5123.
1.01	7.00	14	.01	0.00	.01	5	1.02	20.30	89	.09	.01	.08	5673.
1.01	7.30	15	.01	0.00	.01	5	1.02	21.00	90	.09	.01	.08	6214.
1.01	8.00	16	.01	0.00	.01	5	1.02	21.30	91	.09	.01	.08	6746.
1.01	8.30	17	.01	0.00	.01	4	1.02	22.00	92	.09	.01	.08	7265.
1.01	9.00	18	.01	0.00	.01	4	1.02	22.30	93	.09	.01	.08	7768.
1.01	9.30	19	.01	0.00	.01	4	1.02	23.00	94	.09	.01	.08	8252.
1.01	10.00	20	.01	0.00	.01	4	1.02	23.30	95	.09	.01	.08	8712.
1.01	10.30	21	.01	0.00	.01	3	1.03	0.00	96	.09	.01	.08	9145.
1.01	11.00	22	.01	0.00	.01	3	1.03	1.30	97	.00	.00	.00	9547.
1.01	11.30	23	.01	0.00	.01	3	1.03	1.00	98	.00	.00	.00	9914.
1.01	12.00	24	.01	0.00	.01	3	1.03	1.30	99	.00	.00	.00	10236.
1.01	12.30	25	.07	0.00	.07	2	1.03	2.00	100	.00	.00	.00	10504.
1.01	13.00	26	.07	0.00	.07	2	1.03	2.30	101	.00	.00	.00	10712.
1.01	13.30	27	.08	0.00	.08	2	1.03	3.00	102	.00	.00	.00	10860.
1.01	14.00	28	.08	0.00	.08	2	1.03	3.30	103	.00	.00	.00	10949.
1.01	14.30	29	.10	0.00	.10	2	1.03	4.00	104	.00	.00	.00	10981.
1.01	15.00	30	.10	0.00	.10	2	1.03	4.30	105	.00	.00	.00	10960.
1.01	15.30	31	.13	0.00	.13	2	1.03	5.00	106	.00	.00	.00	10888.
1.01	16.00	32	.40	0.00	.40	2	1.03	5.30	107	.00	.00	.00	10769.
1.01	16.30	33	.10	0.00	.10	1	1.03	6.00	108	.00	.00	.00	10605.
1.01	17.00	34	.10	0.00	.10	1	1.03	6.30	109	.00	.00	.00	10397.
1.01	17.30	35	.08	0.00	.08	1	1.03	7.00	110	.00	.00	.00	10143.
1.01	18.00	36	.08	0.00	.08	1	1.03	7.30	111	.00	.00	.00	9842.
1.01	18.30	37	.01	0.00	.01	1	1.03	8.00	112	.00	.00	.00	9491.
1.01	19.00	38	.01	0.00	.01	1	1.03	8.30	113	.00	.00	.00	9095.
1.01	19.30	39	.01	0.00	.01	1	1.03	9.00	114	.00	.00	.00	8658.
1.01	20.00	40	.01	0.00	.01	1	1.03	9.30	115	.00	.00	.00	8182.
1.01	20.30	41	.01	0.00	.01	1	1.03	10.00	116	.00	.00	.00	7670.
1.01	21.00	42	.01	0.00	.01	1	1.03	10.30	117	.00	.00	.00	7121.
1.01	21.30	43	.01	0.00	.01	1	1.03	11.00	118	.00	.00	.00	6533.
1.01	22.00	44	.01	0.00	.01	1	1.03	11.30	119	.00	.00	.00	5938.
1.01	22.30	45	.01	0.00	.01	1	1.03	12.00	120	.00	.00	.00	5370.
1.01	23.00	46	.01	0.00	.01	1	1.03	12.30	121	.00	.00	.00	4835.
1.01	23.30	47	.01	0.00	.01	1	1.03	13.00	122	.00	.00	.00	4338.
1.02	0.00	48	.01	0.00	.01	1	1.03	13.30	123	.00	.00	.00	3887.
1.02	.30	49	.06	0.00	.06	1	1.03	14.00	124	.00	.00	.00	3482.
1.02	1.00	50	.06	0.00	.06	1	1.03	14.30	125	.00	.00	.00	3119.
1.02	1.30	51	.06	0.00	.06	1	1.03	15.00	126	.00	.00	.00	2794.
1.02	2.00	52	.06	0.00	.06	1	1.03	15.30	127	.00	.00	.00	2503.
1.02	2.30	53	.06	0.00	.06	1	1.03	16.00	128	.00	.00	.00	2242.
1.02	3.00	54	.06	0.00	.06	1	1.03	16.30	129	.00	.00	.00	2007.
1.02	3.30	55	.06	0.00	.06	1	1.03	17.00	130	.00	.00	.00	1797.
1.02	4.00	56	.06	0.00	.06	1	1.03	17.30	131	.00	.00	.00	1608.
1.02	4.30	57	.06	0.00	.06	1	1.03	18.00	132	.00	.00	.00	1439.
1.02	5.00	58	.06	0.00	.06	1	1.03	18.30	133	.00	.00	.00	1286.
1.02	5.30	59	.06	0.00	.06	1	1.03	19.00	134	.00	.00	.00	1150.
1.02	6.00	60	.06	0.00	.06	1	1.03	19.30	135	.00	.00	.00	1028.
1.02	6.30	61	.17	.09	.08	3	1.03	20.00	136	.00	.00	.00	918.
1.02	7.00	62	.17	.09	.08	3	1.03	20.30	137	.00	.00	.00	821.
1.02	7.30	63	.17	.09	.08	7	1.03	21.00	138	.00	.00	.00	733.
1.02	8.00	64	.17	.09	.08	14	1.03	21.30	139	.00	.00	.00	655.

STATION	DAKE	5400.	5500.	5600.	5700.	5800.	5900.	6000.	6100.	6200.	6300.	6400.	0.
51.260	260	5922.						6019.	-97.	-625.	-1.		
51.270	270	5941.						6040.	-99.	-724.	-1.		
51.280	280	5961.						6060.	-99.	-823.	-1.		
51.290	290	5980.						6078.	-98.	-921.	-1.		
51.300	300	5999.						6095.	-96.	-1017.	-1.		
51.310	310	6018.						6111.	-93.	-1110.	-1.		
51.320	320	6037.						6125.	-88.	-1198.	-1.		
51.330	330	6056.						6138.	-82.	-1280.	-1.		
51.340	340	6075.						6151.	-75.	-1356.	-1.		
51.350	350	6094.						6162.	-68.	-1424.	-1.		
51.360	360	6113.						6173.	-59.	-1483.	-1.		
51.370	370	6133.						6183.	-50.	-1533.	-1.		
51.380	380	6152.						6192.	-41.	-1574.	-1.		
51.390	390	6171.						6201.	-31.	-1605.	-1.		
51.400	400	6190.						6210.	-20.	-1624.	-1.		
51.410	410	6209.						6218.	-9.	-1633.	-1.		
51.420	420	6228.						6226.	2.	-1631.	-1.		
51.430	430	6247.						6233.	14.	-1617.	-1.		
51.440	440	6266.						6240.	26.	-1591.	-1.		
51.450	450	6285.						6250.	35.	-1556.	-1.		
51.460	460	6305.						6284.	21.	-1535.	-1.		
51.470	470	6324.						6313.	10.	-1525.	-1.		
51.480	480	6343.						6339.	4.	-1521.	-1.		
51.490	490	6362.						6361.	0.	-1520.	-1.		
51.500	500	6381.						6381.	0.	-1520.	-1.		

180VFS

STATION DAKE

TIME (HRS)	(O) INTERPOLATED BREACH HYDROGRAPH	(B) COMPUTED BREACH HYDROGRAPH	(*) POINTS AT NORMAL TIME INTERVAL
51.00	1.	5400.	0.
51.01	2.	5500.	0.
51.02	3.		0.
51.03	4.		0.
51.04	5.		0.
51.05	6.		0.
51.06	7.		0.
51.07	8.		0.
51.08	9.		0.
51.09	10.		0.
51.10	11.		0.
51.11	12.		0.
51.12	13.		0.
51.13	14.		0.
51.14	15.		0.
51.15	16.		0.
51.16	17.		0.
51.17	18.		0.
51.18	19.		0.
51.19	20.		0.
51.20	21.		0.
51.21	22.		0.
51.22	23.		0.
51.23	24.		0.
51.24	25.		0.
51.25	26.		0.
51.26	27.		0.
51.27	28.		0.
51.28	29.		0.
51.29	30.		0.
51.30	31.		0.
51.31	32.		0.
51.32	33.		0.
51.33	34.		0.

AC-FT 2680. 70 7503 7504
THOUS CU M 3306. 8685. 9255. 9256.

MAXIMUM STORAGE = 25.

MAXIMUM STAGE IS 118.0

STATION REACH1, PLAN 2, RTIO 1

		OUTFLOW									
		5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
7.	7.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.
2.	2.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
59.	72.	87.	108.	138.	184.	237.	311.	400.	521.	672.	864.
672.	864.	1118.	1404.	1661.	1931.	2212.	2487.	2784.	3037.	3303.	3566.
3303.	3566.	3818.	4064.	4291.	4513.	4731.	4926.	5087.	5229.	5337.	5418.
5337.	5418.	5468.	5490.	5484.	5453.	5398.	5320.	5220.	5098.	4952.	4781.
4952.	4781.	4595.	4395.	4159.	3901.	3636.	3343.	3047.	2744.	2475.	2238.
2475.	2238.	2003.	1791.	1608.	1436.	1291.	1153.	1035.	946.	857.	764.
857.	764.	641.	547.	488.	436.	390.	349.	311.	274.	241.	210.
241.	210.	194.	183.	171.	159.	148.	137.	126.	115.	104.	93.

STOR

		STOR									
		5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
7.	7.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.
2.	2.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.
21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.
19.	18.	17.	16.	15.	14.	13.	12.	11.	10.	9.	8.
8.	7.	6.	5.	4.	3.	2.	1.	0.	0.	0.	0.
4.	3.	2.	1.	0.	0.	0.	0.	0.	0.	0.	0.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.

STAGE

		STAGE									
		5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
7.	7.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.	3.
2.	2.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.
11.	12.	13.	14.	15.	16.	17.	18.	19.	20.	21.	22.
21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.	32.
19.	18.	17.	16.	15.	14.	13.	12.	11.	10.	9.	8.
8.	7.	6.	5.	4.	3.	2.	1.	0.	0.	0.	0.
4.	3.	2.	1.	0.	0.	0.	0.	0.	0.	0.	0.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.

PEAK 5490. 5328. 1255. 180727.
CFS 155. 151. 36 5118
CMS 100

TOTAL VOLUME

INCHES
MM
AC-FT
THOUS CU M

3.49	24	9.86	9.87
88.65	234.80	250.56	250.60
2642.	6997.	7467.	7468.
3259.	8631.	9210.	9212.

MAXIMUM STORAGE = 22.

MAXIMUM STAGE IS 117.6

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION STATION AREA PLAN RATIO 1
50

HYDROGRAPH AT LAKE 14.20 1 5491.
(36.78) (155.48)(
2 5491.
(155.48)(

ROUTED TO DAME 14.20 1 6381.
(36.78) (180.69)(
2 5490.
(155.47)(

ROUTED TO REACH1 14.20 1 6196.
(36.78) (175.45)(
2 5490.
(155.45)(

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	132.00	132.00	137.60
OUTFLOW	23.	23.	68.
	0.	0.	4634.

RATIO OF PMF	MAXIMUM RESERVOIR W. S. ELEV	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
50	137.85	70.	6381.	3.17	51.50	51.00

PLAN 2

ELEVATION	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
STORAGE	132.00	132.00	137.60
OUTFLOW	23.	23.	68.
	0.	0.	4634.

RATIO	MAXIMUM	MAXIMUM	MAXIMUM	DURATION	TIME OF	TIME OF

OF PMF	RESERVOIR W.S. ELEV	DEPTH OVER DAM	STORAGE AC-FT	OUTFLOW CFS	OVER TOP HOURS	MAX OUTFLOW HOURS	FAILURE HOURS
50	137.87	27	71	5490	8.00	52.00	0.00

PLAN 1 STATION REACH1

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
50	6196	118.0	51.50

PLAN 2 STATION REACH1

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
50	5490	117.6	52.00

